

Quote No: SQ-20251002-001
Date: 02 Oct 2025

Client:

Name Surname Company Name City, State, PIN Phone | Email

System Overview

Proposed on-grid solar PV system sized at ~5.0 kW with Mono PERC/TOPCon panels and string inverter. Assumptions include south-facing tilt and typical cable runs for an RCC roof.

Bill of Quantities (BOQ)

Description	Brand/Model	Qty	Unit	Amount (₹)
Modules 420 Wp Mono PERC	Any Brand-420	12	Nos	1,68,000
String Inverter ~5kW	Any Brand-5K	1	Nos	48,000
Aluminium Structure		1	Lot	22,000
DC/AC Protection, Cabling		1	Lot	18,000
Design, Installation & Testing		1	Lot	24,000

Price Breakup

Pre-GST: ₹ 2,80,000 GST (indicative): ₹ 24,920 Total: ₹ 3,04,920

Payment Milestones

35% advance with order • 50% on material delivery • 15% on commissioning & handover

Warranty & Terms

Panel performance 25 yrs, product warranty as per OEM. Inverter 5 yrs. Standard exclusions apply. Quote valid for 14 days. Net-metering facilitation as per DISCOM policy.

Acceptance

Client Name & Signature